

Large Scale Site Inspections (LSSI)

Department of Environmental Quality
Office of Training Services



1

Your Instructor



Nick Shrewsbury, DEQ OTS

Nicholaus.shrewsbury@deq.virginia.gov

Questions: certification@deq.virginia.gov



2

Ground Rules

- Silence your cell phones
- Ask questions, engage with groups
- Groups of five people, please
- Speak and share your thoughts
- Be supportive of all participants
 - *Let's do a quick intro roundtable!*



3



<https://www.deq.virginia.gov/our-programs/training-certification/continuing-education>

Large Scale Construction Site Inspections (Full - Fredericksburg)	04/07/2025 8:30 AM - 4:30 PM
Refresher for Inspectors (Full - Fairfax)	05/28/2025 8:30 AM - 4:30 PM
Regulatory SWPPP Inspections (Fairfax)	05/29/2025 8:30 AM - 4:30 PM
Large Scale Construction Site Inspections (Wytheville)	06/18/2025 8:30 AM - 4:30 PM
Using the Virginia Stormwater Management Handbook (Hampton)	07/09/2025 8:30 AM - 4:30 PM
Using the Virginia Stormwater Management Handbook (Richmond)	08/13/2025 8:30 AM - 4:30 PM
Large Scale Construction Site Inspections (Chesapeake)	09/09/2025 8:30 AM - 4:30 PM



4

The purpose of this class

Six contact hours are given for completing this course. Hours earned may be applied to ESC/SWM/Dual Inspector recertification. No partial credit is given



This isn't the class you're looking for.



5

Course Sections

1. Inspection Preparation
2. SWPPP Overview Part I
3. Critical Plan Reading Skills for Large Sites
 - Plan Reading Activity
4. SWPPP Overview Part II
5. Documenting "Site Walk" Observations
 - Site Walk Activity



6

Agenda

- Morning: Intro and Preparing for Inspections
- Break: 10am
- Mid-morning: Comparing “typical” inspections to LSSI
- Lunch: 12pm
- After lunch: Reviewing frequently changing SWPPP documentation and plans for LSSI
- Break: 2:30pm
- Afternoon: Site walk and field observations



7

Learning Objectives

- Being prepared for LSSI before leaving the office
- Understanding how SWPPPs differ on large sites
- Familiarizing yourself with large ESC/SWM plans and tactics for directing field inspections
- Determine priority inspection areas through all phases of construction
- Understanding the process from ESC measures to SWM control installations



8

Large Scale Site Inspection – Section 1

Inspection Preparation



9

What is a Large Scale Construction Site?

- **100+ acres sites**
 - Solar Farms
 - Data Centers
 - Distribution Centers
 - Large Subdivisions
 - Other examples?

LSSI | Section I: Inspection Preparation



10

What's the difference?



1 acre= 43,560 sq. feet



250 acres= 10,890,000 sq. feet

LSSI | Section I: Inspection Preparation



11

What's the difference?



1 acre= 43,560 sq. feet

250 acres= 10,890,000 sq. feet

LSSI | Section I: Inspection Preparation



12

What's the difference?

- So, what do you guys think?

LSSI | Section I: Inspection Preparation



13

What's the difference?

- So, what do you guys think?

LARGER vs "TRADITIONAL" SITES

- Rising Complexity
- Increased Risk/Hazards
- More SWPPP Documentation
- Longer Timeframes
- Requires Detailed Sequencing/Phasing
- Inspectors **MUST** be organized

LSSI | Section I: Inspection Preparation



14


Preparing for the Inspection

Larger sites take longer to inspect



Preparation is **critical!**

- Try not to get overwhelmed



LSSI | Section I: Inspection Preparation



15

Preparing for the Inspection

The **Who, What, Where, Why, and How???**



LSSI | Section I: Inspection Preparation



16

Preparing for the Inspection

• **Who:**

- Is the Operator/permittee?
- Are the Duly Authorized Representatives?
- Are the Qualified Personnel inspecting the site?
- Is your site contact person?
- Will be part of the inspection?



LSSI | Section I: Inspection Preparation



17

Preparing for the Inspection

• **What:**

- Is the size/nature of the project?
- Are the entry/safety protocols?
- Equipment is needed?
- Are previous or ongoing issues?
- Can reasonably be accomplished (*ultimate goal*)?



LSSI | Section I: Inspection Preparation



18

Preparing for the Inspection

- **Where:**

- Are the site points of ingress/egress?
- Is the meeting area (if applicable)?
- Emergency information?
- Is site documentation?
- Are sensitive areas?
- Are all stormwater discharge points?




LSSI | Section I: Inspection Preparation

19

Preparing for the Inspection

- **Why:**

- Is there a need for team effort?
- Would some areas be prioritized?
- Is documentation *MORE* critical on LSSIs?
- Is communication between parties is essential?
- Do we need to keep practical LSSI in perspective?



LSSI | Section I: Inspection Preparation



20

Preparing for the Inspection

- **How:**

- To manage inspection time efficiently?
- To determine inspection priorities?
- Will issues be documented and addressed?
- Can dialog between parties be facilitated?
- Will compliance best achieved?



LSSI | Section I: Inspection Preparation



21

Final Preparation

Do you have the proper PPE?

- Hard Hat
- Safety Glasses
- Hi-Vis Vest
- Gloves
- "These boots were made for walking"...but are they?
- Insect Repellent, Sunscreen
- Site/Company specific reqs. (steel vs composite-toe boots, FR material, safety debriefs)



LSSI | Section I: Inspection Preparation



22

But Wait There's More

- Notebook, Pens, Pencils
- Camera/Phone Fully Charged and Staying Charged
- Weather Considerations (hot, cold, rain, etc.)?
 - Phone Overheating (Summer)
 - Layered Clothing (Winter)
 - Waterproof Equipment (Rain)
- Travel Time to/from Project
- Hydrate, Hydrate, Hydrate



LSSI | Section I: Inspection Preparation



23

Wait....WHERE AGAIN?

- **Where:**

- **PLAN** YOUR INSPECTION!!
 - What's the route?
 - ESC measures
 - Sensitive areas
 - Discharge points
 - Disturbed areas
 - Others? Meeting points, SWPPP, etc.
- Take the TIME to prep!



LSSI | Section I: Inspection Preparation



24

Questions?



LSSI | Section 1: Inspection Preparation



25


Large Scale Site Inspection – Section 2

SWPPP Overview



26

SWPPP Overview Part I



LSSI | Section 2: SWPPP Overview Part I



27

SWPPP Documentation


1. General information	2. Approved ESC plan	3. Approved SWM plan
4. P2 plan	5. Impaired waters, or sediment/nutrient TMDL, + Exceptional	6. PCB impaired waters and TMDL requirements
7. Turbidity Monitoring Requirements	8. Qualified personnel	9. Duly Authorized Representative
10. SWPPP signature	11. SWPPP inspection records	12. Amendments, Modifications, & Updates

LSSI | Section 2: SWPPP Overview Part I



28

SWPPP Overview



LSSI | Section 2: SWPPP Overview Part I



29

SWPPP Documentation - *Static*

1. General information	2. Approved ESC plan	3. Approved SWM plan
4. P2 plan	5. Impaired waters, or sediment/nutrient TMDL, + Exceptional	6. PCB impaired waters and TMDL requirements
7. Turbidity Monitoring Requirements	8. Qualified personnel	9. Duly Authorized Representative
10. SWPPP signature	11. SWPPP inspection records	12. Amendments, Modifications, & Updates

LSSI | Section 2: SWPPP Overview Part I




30

SWPPP Documentation - *Static*

1. General information	1a. Registration Statement	1b. Copy of Notice of Coverage
1c. Copy of the Construction General Permit	1d. Project Narrative	1e. Legible Site Plan


LSSI | Section 2: SWPPP Overview Part I




31

SWPPP Documentation - *Static*

1. General information
1a. Registration Statement




LSSI | Section 2: SWPPP Overview Part I




32

SWPPP Documentation - *Static*

1. General information
1b. Copy of Notice of Coverage




LSSI | Section 2: SWPPP Overview Part I




33

SWPPP Documentation - *Static*

1. General information
1c. Copy of the Construction General Permit




LSSI | Section 2: SWPPP Overview Part I




34

SWPPP Documentation - *Static*

1. General information
1d. Project Narrative




LSSI | Section 2: SWPPP Overview Part I




35

SWPPP Documentation - *Static*

1. General information
1e. Legible Site Plan



LSSI | Section 2: SWPPP Overview Part I




36


SWPPP Documentation - *Static*

1. General information

1e. Legible Site Plan



Key LSSI Point: Clearly, a LOT more updates to handle when keeping a site plan "legible"




LSSI | Section 2: SWPPP Overview Part I

37


SWPPP Documentation - *Static*

1. General information

1e. Legible Site Plan



Key LSSI Point: Size increases = EVEN MORE! updates to handle when keeping a site plan "legible"




LSSI | Section 2: SWPPP Overview Part I

38


SWPPP Documentation - *Static*

2. Approved ESC plan



Approved

Key LSSI Point: Are there modifications to the approved plan? Potentially many, all over the site




LSSI | Section 2: SWPPP Overview Part I

39

SWPPP Documentation - *Static*

2. Approved ESC plan



Key LSSI Point: Scale = SO many MORE to check

CONTROL MEASURES

ALL EROSION AND SEDIMENT CONTROL PRACTICES SHALL BE CONSTRUCTED AT SECOND EDITION, 1992 (VESH-01). THE FOLLOWING PRACTICES ARE PROPOSED:

TEMPORARY EROSION CONTROL PRACTICES: SEE VESH-01, 3.02, 3.03, AND 3.04 FROM PUBLIC ROADWAYS TO STABILIZE THE ACCESS POINT AND ALONE AS SPECIFIED HEREIN. GRAVEL CONSTRUCTION ENTRANCES SHALL BE 6-INCHES THICK AND A MINIMUM OF 70 FEET LONG. A LAYER OF FILTER CLOTH SHALL BE PLACED OVER THE GRAVEL. AN OPTIONAL WASH RACK MAY BE USED IF CONDITIONS REQUIRE IT. WASH RACKS SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOW OF ENTRANCE WITH ADDITIONAL STONE OR REPAIRING THE EXISTING STONE.


SILT FENCE OF VESH-01, 3.05, 3.06, 3.07, 3.08, 3.09, 3.10, 3.11, 3.12, 3.13, 3.14, 3.15, 3.16, 3.17, 3.18, 3.19, 3.20, 3.21, 3.22, 3.23, 3.24, 3.25, 3.26, 3.27, 3.28, 3.29, 3.30, 3.31, 3.32, 3.33, 3.34, 3.35, 3.36, 3.37, 3.38, 3.39, 3.40, 3.41, 3.42, 3.43, 3.44, 3.45, 3.46, 3.47, 3.48, 3.49, 3.50, 3.51, 3.52, 3.53, 3.54, 3.55, 3.56, 3.57, 3.58, 3.59, 3.60, 3.61, 3.62, 3.63, 3.64, 3.65, 3.66, 3.67, 3.68, 3.69, 3.70, 3.71, 3.72, 3.73, 3.74, 3.75, 3.76, 3.77, 3.78, 3.79, 3.80, 3.81, 3.82, 3.83, 3.84, 3.85, 3.86, 3.87, 3.88, 3.89, 3.90, 3.91, 3.92, 3.93, 3.94, 3.95, 3.96, 3.97, 3.98, 3.99, 4.00, 4.01, 4.02, 4.03, 4.04, 4.05, 4.06, 4.07, 4.08, 4.09, 4.10, 4.11, 4.12, 4.13, 4.14, 4.15, 4.16, 4.17, 4.18, 4.19, 4.20, 4.21, 4.22, 4.23, 4.24, 4.25, 4.26, 4.27, 4.28, 4.29, 4.30, 4.31, 4.32, 4.33, 4.34, 4.35, 4.36, 4.37, 4.38, 4.39, 4.40, 4.41, 4.42, 4.43, 4.44, 4.45, 4.46, 4.47, 4.48, 4.49, 4.50, 4.51, 4.52, 4.53, 4.54, 4.55, 4.56, 4.57, 4.58, 4.59, 4.60, 4.61, 4.62, 4.63, 4.64, 4.65, 4.66, 4.67, 4.68, 4.69, 4.70, 4.71, 4.72, 4.73, 4.74, 4.75, 4.76, 4.77, 4.78, 4.79, 4.80, 4.81, 4.82, 4.83, 4.84, 4.85, 4.86, 4.87, 4.88, 4.89, 4.90, 4.91, 4.92, 4.93, 4.94, 4.95, 4.96, 4.97, 4.98, 4.99, 5.00, 5.01, 5.02, 5.03, 5.04, 5.05, 5.06, 5.07, 5.08, 5.09, 5.10, 5.11, 5.12, 5.13, 5.14, 5.15, 5.16, 5.17, 5.18, 5.19, 5.20, 5.21, 5.22, 5.23, 5.24, 5.25, 5.26, 5.27, 5.28, 5.29, 5.30, 5.31, 5.32, 5.33, 5.34, 5.35, 5.36, 5.37, 5.38, 5.39, 5.40, 5.41, 5.42, 5.43, 5.44, 5.45, 5.46, 5.47, 5.48, 5.49, 5.50, 5.51, 5.52, 5.53, 5.54, 5.55, 5.56, 5.57, 5.58, 5.59, 5.60, 5.61, 5.62, 5.63, 5.64, 5.65, 5.66, 5.67, 5.68, 5.69, 5.70, 5.71, 5.72, 5.73, 5.74, 5.75, 5.76, 5.77, 5.78, 5.79, 5.80, 5.81, 5.82, 5.83, 5.84, 5.85, 5.86, 5.87, 5.88, 5.89, 5.90, 5.91, 5.92, 5.93, 5.94, 5.95, 5.96, 5.97, 5.98, 5.99, 6.00, 6.01, 6.02, 6.03, 6.04, 6.05, 6.06, 6.07, 6.08, 6.09, 6.10, 6.11, 6.12, 6.13, 6.14, 6.15, 6.16, 6.17, 6.18, 6.19, 6.20, 6.21, 6.22, 6.23, 6.24, 6.25, 6.26, 6.27, 6.28, 6.29, 6.30, 6.31, 6.32, 6.33, 6.34, 6.35, 6.36, 6.37, 6.38, 6.39, 6.40, 6.41, 6.42, 6.43, 6.44, 6.45, 6.46, 6.47, 6.48, 6.49, 6.50, 6.51, 6.52, 6.53, 6.54, 6.55, 6.56, 6.57, 6.58, 6.59, 6.60, 6.61, 6.62, 6.63, 6.64, 6.65, 6.66, 6.67, 6.68, 6.69, 6.70, 6.71, 6.72, 6.73, 6.74, 6.75, 6.76, 6.77, 6.78, 6.79, 6.80, 6.81, 6.82, 6.83, 6.84, 6.85, 6.86, 6.87, 6.88, 6.89, 6.90, 6.91, 6.92, 6.93, 6.94, 6.95, 6.96, 6.97, 6.98, 6.99, 7.00, 7.01, 7.02, 7.03, 7.04, 7.05, 7.06, 7.07, 7.08, 7.09, 7.10, 7.11, 7.12, 7.13, 7.14, 7.15, 7.16, 7.17, 7.18, 7.19, 7.20, 7.21, 7.22, 7.23, 7.24, 7.25, 7.26, 7.27, 7.28, 7.29, 7.30, 7.31, 7.32, 7.33, 7.34, 7.35, 7.36, 7.37, 7.38, 7.39, 7.40, 7.41, 7.42, 7.43, 7.44, 7.45, 7.46, 7.47, 7.48, 7.49, 7.50, 7.51, 7.52, 7.53, 7.54, 7.55, 7.56, 7.57, 7.58, 7.59, 7.60, 7.61, 7.62, 7.63, 7.64, 7.65, 7.66, 7.67, 7.68, 7.69, 7.70, 7.71, 7.72, 7.73, 7.74, 7.75, 7.76, 7.77, 7.78, 7.79, 7.80, 7.81, 7.82, 7.83, 7.84, 7.85, 7.86, 7.87, 7.88, 7.89, 7.90, 7.91, 7.92, 7.93, 7.94, 7.95, 7.96, 7.97, 7.98, 7.99, 8.00, 8.01, 8.02, 8.03, 8.04, 8.05, 8.06, 8.07, 8.08, 8.09, 8.10, 8.11, 8.12, 8.13, 8.14, 8.15, 8.16, 8.17, 8.18, 8.19, 8.20, 8.21, 8.22, 8.23, 8.24, 8.25, 8.26, 8.27, 8.28, 8.29, 8.30, 8.31, 8.32, 8.33, 8.34, 8.35, 8.36, 8.37, 8.38, 8.39, 8.40, 8.41, 8.42, 8.43, 8.44, 8.45, 8.46, 8.47, 8.48, 8.49, 8.50, 8.51, 8.52, 8.53, 8.54, 8.55, 8.56, 8.57, 8.58, 8.59, 8.60, 8.61, 8.62, 8.63, 8.64, 8.65, 8.66, 8.67, 8.68, 8.69, 8.70, 8.71, 8.72, 8.73, 8.74, 8.75, 8.76, 8.77, 8.78, 8.79, 8.80, 8.81, 8.82, 8.83, 8.84, 8.85, 8.86, 8.87, 8.88, 8.89, 8.90, 8.91, 8.92, 8.93, 8.94, 8.95, 8.96, 8.97, 8.98, 8.99, 9.00, 9.01, 9.02, 9.03, 9.04, 9.05, 9.06, 9.07, 9.08, 9.09, 9.10, 9.11, 9.12, 9.13, 9.14, 9.15, 9.16, 9.17, 9.18, 9.19, 9.20, 9.21, 9.22, 9.23, 9.24, 9.25, 9.26, 9.27, 9.28, 9.29, 9.30, 9.31, 9.32, 9.33, 9.34, 9.35, 9.36, 9.37, 9.38, 9.39, 9.40, 9.41, 9.42, 9.43, 9.44, 9.45, 9.46, 9.47, 9.48, 9.49, 9.50, 9.51, 9.52, 9.53, 9.54, 9.55, 9.56, 9.57, 9.58, 9.59, 9.60, 9.61, 9.62, 9.63, 9.64, 9.65, 9.66, 9.67, 9.68, 9.69, 9.70, 9.71, 9.72, 9.73, 9.74, 9.75, 9.76, 9.77, 9.78, 9.79, 9.80, 9.81, 9.82, 9.83, 9.84, 9.85, 9.86, 9.87, 9.88, 9.89, 9.90, 9.91, 9.92, 9.93, 9.94, 9.95, 9.96, 9.97, 9.98, 9.99, 10.00, 10.01, 10.02, 10.03, 10.04, 10.05, 10.06, 10.07, 10.08, 10.09, 10.10, 10.11, 10.12, 10.13, 10.14, 10.15, 10.16, 10.17, 10.18, 10.19, 10.20, 10.21, 10.22, 10.23, 10.24, 10.25, 10.26, 10.27, 10.28, 10.29, 10.30, 10.31, 10.32, 10.33, 10.34, 10.35, 10.36, 10.37, 10.38, 10.39, 10.40, 10.41, 10.42, 10.43, 10.44, 10.45, 10.46, 10.47, 10.48, 10.49, 10.50, 10.51, 10.52, 10.53, 10.54, 10.55, 10.56, 10.57, 10.58, 10.59, 10.60, 10.61, 10.62, 10.63, 10.64, 10.65, 10.66, 10.67, 10.68, 10.69, 10.70, 10.71, 10.72, 10.73, 10.74, 10.75, 10.76, 10.77, 10.78, 10.79, 10.80, 10.81, 10.82, 10.83, 10.84, 10.85, 10.86, 10.87, 10.88, 10.89, 10.90, 10.91, 10.92, 10.93, 10.94, 10.95, 10.96, 10.97, 10.98, 10.99, 11.00, 11.01, 11.02, 11.03, 11.04, 11.05, 11.06, 11.07, 11.08, 11.09, 11.10, 11.11, 11.12, 11.13, 11.14, 11.15, 11.16, 11.17, 11.18, 11.19, 11.20, 11.21, 11.22, 11.23, 11.24, 11.25, 11.26, 11.27, 11.28, 11.29, 11.30, 11.31, 11.32, 11.33, 11.34, 11.35, 11.36, 11.37, 11.38, 11.39, 11.40, 11.41, 11.42, 11.43, 11.44, 11.45, 11.46, 11.47, 11.48, 11.49, 11.50, 11.51, 11.52, 11.53, 11.54, 11.55, 11.56, 11.57, 11.58, 11.59, 11.60, 11.61, 11.62, 11.63, 11.64, 11.65, 11.66, 11.67, 11.68, 11.69, 11.70, 11.71, 11.72, 11.73, 11.74, 11.75, 11.76, 11.77, 11.78, 11.79, 11.80, 11.81, 11.82, 11.83, 11.84, 11.85, 11.86, 11.87, 11.88, 11.89, 11.90, 11.91, 11.92, 11.93, 11.94, 11.95, 11.96, 11.97, 11.98, 11.99, 12.00, 12.01, 12.02, 12.03, 12.04, 12.05, 12.06, 12.07, 12.08, 12.09, 12.10, 12.11, 12.12, 12.13, 12.14, 12.15, 12.16, 12.17, 12.18, 12.19, 12.20, 12.21, 12.22, 12.23, 12.24, 12.25, 12.26, 12.27, 12.28, 12.29, 12.30, 12.31, 12.32, 12.33, 12.34, 12.35, 12.36, 12.37, 12.38, 12.39, 12.40, 12.41, 12.42, 12.43, 12.44, 12.45, 12.46, 12.47, 12.48, 12.49, 12.50, 12.51, 12.52, 12.53, 12.54, 12.55, 12.56, 12.57, 12.58, 12.59, 12.60, 12.61, 12.62, 12.63, 12.64, 12.65, 12.66, 12.67, 12.68, 12.69, 12.70, 12.71, 12.72, 12.73, 12.74, 12.75, 12.76, 12.77, 12.78, 12.79, 12.80, 12.81, 12.82, 12.83, 12.84, 12.85, 12.86, 12.87, 12.88, 12.89, 12.90, 12.91, 12.92, 12.93, 12.94, 12.95, 12.96, 12.97, 12.98, 12.99, 13.00, 13.01, 13.02, 13.03, 13.04, 13.05, 13.06, 13.07, 13.08, 13.09, 13.10, 13.11, 13.12, 13.13, 13.14, 13.15, 13.16, 13.17, 13.18, 13.19, 13.20, 13.21, 13.22, 13.23, 13.24, 13.25, 13.26, 13.27, 13.28, 13.29, 13.30, 13.31, 13.32, 13.33, 13.34, 13.35, 13.36, 13.37, 13.38, 13.39, 13.40, 13.41, 13.42, 13.43, 13.44, 13.45, 13.46, 13.47, 13.48, 13.49, 13.50, 13.51, 13.52, 13.53, 13.54, 13.55, 13.56, 13.57, 13.58, 13.59, 13.60, 13.61, 13.62, 13.63, 13.64, 13.65, 13.66, 13.67, 13.68, 13.69, 13.70, 13.71, 13.72, 13.73, 13.74, 13.75, 13.76, 13.77, 13.78, 13.79, 13.80, 13.81, 13.82, 13.83, 13.84, 13.85, 13.86, 13.87, 13.88, 13.89, 13.90, 13.91, 13.92, 13.93, 13.94, 13.95, 13.96, 13.97, 13.98, 13.99, 14.00, 14.01, 14.02, 14.03, 14.04, 14.05, 14.06, 14.07, 14.08, 14.09, 14.10, 14.11, 14.12, 14.13, 14.14, 14.15, 14.16, 14.17, 14.18, 14.19, 14.20, 14.21, 14.22, 14.23, 14.24, 14.25, 14.26, 14.27, 14.28, 14.29, 14.30, 14.31, 14.32, 14.33, 14.34, 14.35, 14.36, 14.37, 14.38, 14.39, 14.40, 14.41, 14.42, 14.43, 14.44, 14.45, 14.46, 14.47, 14.48, 14.49, 14.50, 14.51, 14.52, 14.53, 14.54, 14.55, 14.56, 14.57, 14.58, 14.59, 14.60, 14.61, 14.62, 14.63, 14.64, 14.65, 14.66, 14.67, 14.68, 14.69, 14.70, 14.71, 14.72, 14.73, 14.74, 14.75, 14.76, 14.77, 14.78, 14.79, 14.80, 14.81, 14.82, 14.83, 14.84, 14.85, 14.86, 14.87, 14.88, 14.89, 14.90, 14.91, 14.92, 14.93, 14.94, 14.95, 14.96, 14.97, 14.98, 14.99, 15.00, 15.01, 15.02, 15.03, 15.04, 15.05, 15.06, 15.07, 15.08, 15.09, 15.10, 15.11, 15.12, 15.13, 15.14, 15.15, 15.16, 15.17, 15.18, 15.19, 15.20, 15.21, 15.22, 15.23, 15.24, 15.25, 15.26, 15.27, 15.28, 15.29, 15.30, 15.31, 15.32, 15.33, 15.34, 15.35, 15.36, 15.37, 15.38, 15.39, 15.40, 15.41, 15.42, 15.43, 15.44, 15.45, 15.46, 15.47, 15.48, 15.49, 15.50, 15.51, 15.52, 15.53, 15.54, 15.55, 15.56, 15.57, 15.58, 15.59, 15.60, 15.61, 15.62, 15.63, 15.64, 15.65, 15.66, 15.67, 15.68, 15.69, 15.70, 15.71, 15.72, 15.73, 15.74, 15.75, 15.76, 15.77, 15.78, 15.79, 15.80, 15.81, 15.82, 15.83, 15.84, 15.85, 15.86, 15.87, 15.88, 15.89, 15.90, 15.91, 15.92, 15.93, 15.94, 15.95, 15.96, 15.97, 15.98, 15.99, 16.00, 16.01, 16.02, 16.03, 16.04, 16.05, 16.06, 16.07, 16.08, 16.09, 16.10, 16.11, 16.12, 16.13, 16.14, 16.15, 16.16, 16.17, 16.18, 16.19, 16.20, 16.21, 16.22, 16.23, 16.24, 16.25, 16.26, 16.27, 16.28, 16.29, 16.30, 16.31, 16.32, 16.33, 16.34, 16.35, 16.36, 16.37, 16.38, 16.39, 16.40, 16.41, 16.42, 16.43, 16.44, 16.45, 16.46, 16.47, 16.48, 16.49, 16.50, 16.51, 16.52, 16.53, 16.54, 16.55, 16.56, 16.57, 16.58, 16.59, 16.60, 16.61, 16.62, 16.63, 16.64, 16.65, 16.66, 16.67, 16.68, 16.69, 16.70, 16.71, 16.72, 16.73, 16.74, 16.75, 16.76, 16.77, 16.78, 16.79, 16.80, 16.81, 16.82, 16.83, 16.84, 16.85, 16.86, 16.87, 16.88, 16.89, 16.90, 16.91, 16.92, 16.93, 16.94, 16.95, 16.96, 16.97, 16.98, 16.99, 17.00, 17.01, 17.02, 17.03, 17.04, 17.05, 17.06, 17.07, 17.08, 17.09, 17.10, 17.11, 17.12, 17.13, 17.14, 17.15, 17.16, 17.17, 17.18, 17.19, 17.20, 17.21, 17.22, 17.23, 17.24, 17.25, 17.26, 17.27, 17.28, 17.29, 17.30, 17.31, 17.32, 17.33, 17.34, 17.35, 17.36, 17.37, 17.38, 17.39, 17.40, 17.41, 17.42, 17.43, 17.44, 17.45, 17.46, 17.47, 17.48, 17.49, 17.50, 17.51, 17.52, 17.53, 17.54, 17.55, 17.56, 17.57, 17.58, 17.59, 17.60, 17.61, 17.62, 17.63, 17.64, 17.65, 17.66, 17.67, 17.68, 17.69, 17.70, 17.71, 17.72, 17.73, 17.74, 17.75, 17.76, 17.77, 17.78, 17.79, 17.80, 17.81, 17.82, 17.83, 17.84, 17.85, 17.86, 17.87, 17.88, 17.89, 17.90, 17.91, 17.92, 17.93, 17.94, 17.95, 17.96, 17.97, 17.98, 17.99, 18.00, 18.01, 18.02, 18.03, 18.04, 18.05, 18.06, 18.07, 18.08, 18.09, 18.10, 18.11, 18.12, 18.13, 18.14, 18.15, 18.16, 18.17, 18.18, 18.19, 18.20, 18.21, 18.22, 18.23, 18.24, 18.25, 18.26, 18.27, 18.28, 18.29, 18.30, 18.31, 18.32, 18.33, 18.34, 18.35, 18.36, 18.37, 18.38, 18.39, 18.40, 18.41, 18.42, 18.43, 18.44, 18.45, 18.46, 18.47, 18.48, 18.49, 18.50, 18.51, 18.52, 18.53, 18.54, 18.55, 18.56, 18.57, 18.58, 18.59, 18.60, 18.61, 18.62, 18.63, 18.64, 18.65, 18.66, 18.67, 18.68, 18.69, 18.70, 18.71, 18.72, 18.73, 18.74, 18.75, 18.76, 18.77, 18.78, 18.79, 18.80, 18.81, 18.82, 18.83, 18.84, 18.85, 18.86, 18.87, 18.88, 18.89, 18.90, 18.91, 18.92, 18.93, 18.94, 18.95, 18.96, 18.97, 18.98, 18.99, 19.00, 19.01, 19.02, 19.03, 19.04, 19.05, 19.06, 19.07, 19.08, 19.09, 19.10, 19.11, 19.12, 19.13, 19.14, 19.15, 19.16, 19.17, 19.18, 19.19, 19.20, 19.21, 19.22, 19.23, 19.24, 19.25, 19.26, 19.27, 19.28, 19.29, 19.30, 19.31, 19.32, 19.33, 19.34, 19.35, 19.36, 19.37, 19.38, 19.39, 19.40, 19.41, 19.42, 19.43, 19.44, 19.45, 19.46, 19.47, 19.48, 19.49, 19.50, 19.51, 19.52, 19.53, 19.54, 19.55, 19.56, 19.57, 19.58, 19.59, 19.60, 19.61, 19.62, 19.63, 19.64, 19.65, 19.66, 19.67, 19.68, 19.69, 19.70, 19.71, 19.72, 19.73, 19.74, 19.75, 19.76, 19.77, 19.78, 19.79, 19.80, 19.81, 19.82, 19.83, 19.84, 1

SWPPP Documentation - Static


2. Approved ESC plan

****Example – Silt Fence**

- LSSI: Is every ESC measure detailed here?



LSSI | Section 2: SWPPP Overview Part I




44

SWPPP Documentation - Static


2. Approved ESC plan

****Example – Silt Fence Proprietary Measure**

- LSSI: Is every ESC measure detailed here?
- Any non-standard practices?



LSSI | Section 2: SWPPP Overview Part I




45


SWPPP Documentation - Static

2. Approved ESC plan

LSSI Key Point:
Very likely there are sensitive area impacts or adjacent to LDA?



LSSI | Section 2: SWPPP Overview Part I




46


SWPPP Documentation - Static

2. Approved ESC plan

LSSI Key Point:
MANY more sediment traps/basins than smaller sites



LSSI | Section 2: SWPPP Overview Part I



47


SWPPP Documentation - Static

2. Approved ESC plan


LSSI Key Point:
MANY more sediment traps/basins than smaller sites

120 acres

- 6 Traps
- 11 Basins



LSSI | Section 2: SWPPP Overview Part I



48

SWPPP Documentation - Static

2. Approved ESC plan


LSSI Key Point:
MANY more sediment traps/basins than smaller sites

440 acres


88!! Sediment Basins

SEE??

!!!!!!



LSSI | Section 2: SWPPP Overview Part I




49

SWPPP Documentation - *Static*

2. Approved ESC plan

LSSI Key Point:
All outfalls/outlet protections should be designed and sized specific to each control measure discharge (ST/SB/pipe/swale)



LSSI | Section 2: SWPPP Overview Part I



50

SWPPP Documentation - *Static*

*Info for inspectors

2. Approved ESC plan

LSSI Key Point:
All outfalls/outlet protections should be designed and sized specific to each control measure discharge (ST/SB/pipe/swale)

DIVERSION DITCH CALCULATION TABLE									
Ditch #	Length	Width/Height	Min Channel Slope (ft/ft)	Max Channel Slope (ft/ft)	Left Side Slope (ft/ft)	Right Side Slope (ft/ft)	Exchange Velocity (ft/hrs)	Velocity (ft/hrs)	VOGT Slope (ft/ft)
D001	97	0.03	0.0022	0.004	3:1	3:1	3.2	3.8	EC-3
D005	143	0.03	0.0027	0.0060	3:1	3:1	3.7	4.60	EC-3A
D016	705	0.03	0.0032	0.0077	3:1	3:1	3.9	6.37	EC-3A
D018	187	0.03	0.0030	0.0035	3:1	3:1	3.3	3.93	EC-2

Culvert Outlet Protection Summary Table									
Culvert #	Pipe size, Do (in)	Q ₁₀ (cfs)	Q ₁₀ (ft/s)	Min. d ₅₀ Stone Size (in)	VOGT RFRAP CLASS	Actual d ₅₀ Stone Size (in)	Min. Stone Depth, d (in)	Min. Length, L _o (ft)	Min. Width (ft)
C30	15	0.69	0.78	6	A1	9.6	21.6	10	3.75
C31	15	1.54	3.97	6	A1	9.6	21.6	10	3.90
C32	15	0.77	0.86	6	A1	9.6	21.6	10	3.75
C33	15	39.53	44.61	6	A1	9.6	21.6	14	4.50
C44	24	25.52	28.93	6	A1	9.6	21.6	14	6.00
C37	15	6.83	7.70	6	A1	9.6	21.6	10	3.75

Basin Outlet Protection Summary Table									
Basin #	Pipe size, Do (in)	Q ₁₀ (cfs)*	Q ₁₀ (ft/s)**	Min. d ₅₀ Stone Size (in)	VOGT RFRAP CLASS	Actual d ₅₀ Stone Size (in)	Min. Stone Depth, d (in)	Min. Length, L _o (ft)	Min. Width (ft)
B002	15	1.66	3.63	6	A1	9.6	21.6	11	3.75
B003	15	1.49	31.06	6	A1	9.6	21.6	13	3.75
B004	15	0.57	4.00	6	A1	9.6	21.6	10	3.75
B005	15	0.21	4.63	6	A1	9.6	21.6	10	3.75

LSSI | Section 2: SWPPP Overview Part I



51

SWPPP Documentation - *Static*

2. Approved ESC plan

Once you understand;

- What ESC measures are being used and;
- How they need to be installed.....



LSSI | Section 2: SWPPP Overview Part I




52

SWPPP Documentation - *Static*

2. Approved ESC plan

WHERE ARE THEY?!

...and Where to start??



LSSI | Section 2: SWPPP Overview Part I




53

SWPPP Documentation - *Static*

2. Approved ESC plan

Preparation and Planning:

- Must understand the overall layout
- But...we have to dig deeper for section information



LSSI | Section 2: SWPPP Overview Part I




54

SWPPP Documentation - *Static*

2. Approved ESC plan

LSSI Key Point:

- What ESC measures have(not) been installed?
- Co-located/Conversion to SWM facilities
- Hotspots – add. controls
- ESC no longer needed
- Disturbed or Active Work Areas across the project



LSSI | Section 2: SWPPP Overview Part I




55

SWPPP Documentation - *Static*

3. Approved SWM plan

- Plan Approval Letter
- Mistaken for required Notice of Coverage letter



The Department of Environmental Quality (DEQ) has reviewed the Erosion and Stormwater Management (ESM) Plan, titled T&C Commercial Development and dated 6/28/24, and revisions dated 7/18/24. This plan was received on June 27, 2024 in accordance with the Virginia Erosion and Stormwater Management Act and the Virginia Erosion and attendant regulations. The ESM Plan dated June 26, 2024 and with the latest revision date of July 18, 2024 is hereby approved and a copy is enclosed. No changes may be made to the approved Plan without obtaining prior approval from DEQ.

LSSI | Section 2: SWPPP Overview Part I



56

SWPPP Documentation - *Static*

3. Approved SWM plan

- Table of Contents

Key Point: Where are the permanent stormwater BMPs?

- LSSI: Again....MANY more

Contents	
1. Project Description	1
2. Existing Site Conditions	1
3. Proposed Site Conditions	2
4. Site Drainage and Hydrology	2
4.1. Existing Site Hydrology and Drainage	2
4.2. SWM Requirements for Proposed Site	3
4.2.1. Wetland	3
4.2.2. Water Quality Requirements	3
4.2.3. Water Quantity Requirements	4
5. Proposed Stormwater Management Plan	4
6.1. Stormwater	4
6. Best Management Practice Designs and Treatment	4
6.1. Cistern	4
6.2. Permeable Pavement	4
6.3. Dry Swale	4
6.4. Extended Detention	4
7. Compliance Summary	5
8. Appendix	10
Appendix A: Water Quality Calculations	10
Appendix B: Water Quantity Calculations	10
Appendix C: Postpeak Flowing Results	10

LSSI | Section 2: SWPPP Overview Part I



57

SWPPP Documentation - *Static*

3. Approved SWM plan

- Water Quality Compliance
- VRRM

Site Land Cover Summary	Acres	Area	Value	Score	% of Total
Impervious Surface	0.00	0.00	0.00	0.00	0.00
Grassland	0.00	0.00	0.00	0.00	0.00
Forest	0.00	0.00	0.00	0.00	0.00
Water	0.00	0.00	0.00	0.00	0.00
Other	0.00	0.00	0.00	0.00	0.00
Total	0.00	0.00	0.00	0.00	0.00

Key compliance check:
Any "conserved areas" designated across the site needing protection?

Remaining TP Load Reduction (lb/yr) Required: **0.00** ** TARGET TP REDUCTION EXCEEDED BY 0.22 LB/YEAR **

LSSI | Section 2: SWPPP Overview Part I



58

SWPPP Documentation - *Static*

3. Approved SWM plan

- Water Quantity Compliance
- Calculations

Key compliance check:
• Channel Protection
• Flood Protection
• Sheet Flow

Appendix B: Water Quantity Calculations
Existing Conditions:
Peak 2 = $\frac{C_u}{C_d} \times \frac{Q_u}{Q_d} = 1.0 \times \frac{1.0}{1.0} = 1.0 \times 2.7 \text{ in.}$
$C_u = \frac{P}{P + 0.001} = \frac{2.6}{2.6 + 0.001} = 0.999$
$C_d = \frac{P}{P + 0.001} = \frac{2.6}{2.6 + 0.001} = 0.999$
$Q_u = 0.001 \times 1.0 \times 1.0 = 0.001 \text{ in.} \times 0.7 \text{ in.} = 0.0007 \text{ in.}$
Proposed Conditions:
Peak 2 = $\frac{C_u}{C_d} \times \frac{Q_u}{Q_d} = 1.0 \times \frac{1.0}{1.0} = 1.0 \times 2.8 \text{ in.}$
$C_u = \frac{P}{P + 0.001} = \frac{2.6}{2.6 + 0.001} = 0.999$
$C_d = \frac{P}{P + 0.001} = \frac{2.6}{2.6 + 0.001} = 0.999$
$Q_u = 0.001 \times 1.0 \times 1.0 = 0.001 \text{ in.} \times 0.7 \text{ in.} = 0.0007 \text{ in.}$
Energy Balance:
$Q_{\text{loss}} = Q_u - Q_d = \frac{Q_u}{C_u} - \frac{Q_d}{C_d}$
$= \frac{0.0007}{0.999} - \frac{0.0007}{0.999}$
$= 0.0007 \text{ in.}$
Attenuation is required.

LSSI | Section 2: SWPPP Overview Part I




59

SWPPP Documentation - *Static*

3. Approved SWM plan

- Stormwater BMP Locations

6. Best Management Practice Designs and Treatment:
6.1. Cistern
6.2. Permeable Pavement
6.3. Dry Swale
6.4. Extended Detention



LSSI | Section 2: SWPPP Overview Part I



60


SWPPP Documentation - *Static*

3. Approved SWM plan

- Stormwater BMP Locations

How are **Large Sites** any different?

> 400 acres



LSSI | Section 2: SWPPP Overview Part I



61


SWPPP Documentation - Static

3. Approved SWM plan

- Stormwater BMP Locations

How are **Large Sites** any different?

> 400 acres



LSSI | Section 2: SWPPP Overview Part I



62


SWPPP Documentation - Static

3. Approved SWM plan

- Stormwater BMP Details

Key inspection check: How is this thing going to *actually* be built?

- LSSI: Ensure **EVERY** BMP is following the plan or changes are documented



LSSI | Section 2: SWPPP Overview Part I



63

SWPPP Documentation - Static

3. Approved SWM plan

- Stormwater BMP Details

- ESC to SWM BMP conversion notes
- Permanent P-BMP information

- SEDIMENT BASIN TO PERMANENT DETENTION BASIN SEQUENCE**
1. DEWATER BASINS AND MUCK OUT SILT. DEWATERING OF THE BASINS SHALL BE DONE IN A NON EROSION MANNER WITH THE USE OF A DIRT BAG (OR EQUIVALENT).
 2. BRING BOTTOM OF BASIN TO PERMANENT GRADE (IF NECESSARY).
 3. COVER THE PERMANENT ORIFICES AND INSTALL ORIFICE TRASH RACKS.
 4. REMOVE THE TEMPORARY DEWATERING DEVICES FROM THE RISERS AND PLUG UP THE ORIFICES.
 5. REMOVE TEMPORARY ANTI-VORTEX DEVICES AND INSTALL PERMANENT TRASH RACKS.
 6. APPLY PERMANENT SEEDING TO ALL DISTURBED AND/OR PREVIOUSLY IRRIGATED AREAS.
 7. BASIN CONVERSIONS SHALL BE CERTIFIED BY A PROFESSIONAL ENGINEER BEFORE THE GENERAL CONSTRUCTION PERMIT IS TERMINATED.
- SEDIMENT TRAP TO PERMANENT DETENTION BASIN SEQUENCE**
1. DEWATER BASINS AND MUCK OUT SILT. DEWATERING OF THE BASINS SHALL BE DONE IN A NON EROSION MANNER WITH THE USE OF A DIRT BAG (OR EQUIVALENT).
 2. BRING BOTTOM OF BASIN TO PERMANENT GRADE (IF NECESSARY).
 3. REMOVE TEMPORARY PLATE ON PIPE AND INSTALL PERMANENT RISER.
 4. REMOVE STONE OUTLET AND INSTALL PERMANENT EMERGENCY SPILLWAY.
 5. APPLY PERMANENT SEEDING TO ALL DISTURBED AND/OR PREVIOUSLY IRRIGATED AREAS.
 6. BASIN CONVERSIONS SHALL BE CERTIFIED BY A PROFESSIONAL ENGINEER BEFORE THE GENERAL CONSTRUCTION PERMIT IS TERMINATED.

PIPE #	DI	FROM - TO	UPSTREAM INVERT	DOWNTHEAM INVERT	SLOPE	LENGTH	DESCRIPTION
D101C-2	24"	D101C-1 - D101C-3	122.20	120.50	2.00%	85.00 LF	24 inch RCP
D103A-2	18"	D103A-1 - D103A-3	109.59	108.51	2.00%	54.00 LF	18" RCP
D104A-2	12"	D104A-1 - D104A-3	113.77	112.99	2.00%	39.00 LF	12" RCP
D105A-2	12"	D105A-1 - D105A-3	119.57	118.75	2.00%	41.00 LF	12" RCP

LSSI | Section 2: SWPPP Overview Part I



64


SWPPP Documentation - Static

PERMANENT BASIN/RISER TYPICAL DETAIL

3. Approved SWM plan

- Stormwater BMP Details

- All BMPs are converted per the SWM Plan (field check)
- Proper materials
 - Watertight connections



LSSI | Section 2: SWPPP Overview Part I



65

SWPPP Documentation - Static

3. Approved SWM plan

- Stormwater BMP Details

- Additional Considerations:
- Other storm pipe installation

PIPE #	DI	FROM - TO	UPSTREAM INVERT	DOWNTHEAM INVERT	SLOPE	LENGTH	DESCRIPTION
D101C-2	24"	D101C-1 - D101C-3	122.20	120.50	2.00%	85.00 LF	24 inch RCP
D103A-2	18"	D103A-1 - D103A-3	109.59	108.51	2.00%	54.00 LF	18" RCP
D104A-2	12"	D104A-1 - D104A-3	113.77	112.99	2.00%	39.00 LF	12" RCP
D105A-2	12"	D105A-1 - D105A-3	119.57	118.75	2.00%	41.00 LF	12" RCP



LSSI | Section 2: SWPPP Overview Part I



66

SWPPP Documentation - Static

3. Approved SWM plan

- Stormwater BMP Details

- Additional Considerations:
- Other storm pipe installation

PIPE #	DI	FROM - TO	UPSTREAM INVERT	DOWNTHEAM INVERT	SLOPE	LENGTH	DESCRIPTION
D101C-2	24"	D101C-1 - D101C-3	122.20	120.50	2.00%	85.00 LF	24 inch RCP
D103A-2	18"	D103A-1 - D103A-3	109.59	108.51	2.00%	54.00 LF	18" RCP
D104A-2	12"	D104A-1 - D104A-3	113.77	112.99	2.00%	39.00 LF	12" RCP
D105A-2	12"	D105A-1 - D105A-3	119.57	118.75	2.00%	41.00 LF	12" RCP

Basin #	Pipe size, (in)	Q ₁₀ (cfs)*	Min. A ₁₀ Stone Size (in)	VCOF R/R/RAIP CLASS	Actual A ₁₀ Stone Size (in)	Min. Slope Depth, d (in)	Min. Slope Length, L _a (ft)	Min. Width (ft)
0001	15	2.06	8.51	6	A1	1.6	21.6	11
0003	15	1.49	11.00	6	A1	1.6	21.6	11
0004	15	0.57	4.06	6	A1	1.6	21.6	11
0005	15	0.31	4.63	6	A1	1.6	21.6	11
0006	15	0.11	0.84	6	A1	1.6	21.6	11

LSSI | Section 2: SWPPP Overview Part I



67

SWPPP Documentation - *Static*

5. Impaired waters, TMDL + exceptional waters requirements

6. PCB impaired waters and TMDL requirements

LSSI key point: Could be discharging into multiple downstream systems

- Are ANY waterways are identified in this section?

SWPPP Inspection Schedule
(VDM 22-0000-70 Part I B 4-6 and Part II G 2)

Discharges to impaired waters, surface waters with an applicable TMDL or exceptional waters	Standard Inspections
Inspections must be conducted either:	Inspections must be conducted either:
1. At least once every 4 business days or	1. At least once every 3 business days or
2. At least once every 3 business days and no later than 24 hours following a measurable stress event	2. At least once every 10 business days and no later than 24 hours following a measurable stress event

LSSI | Section 2: SWPPP Overview Part I

68

SWPPP Documentation - *Static*

8. Qualified personnel

Key inspection check: Who are the people doing SWPPP Inspections for the Operator?

- LSSI: Could be MANY different people

IDENTIFICATION OF QUALIFIED PERSONNEL

First Name: [Blank]
Last Name: [Blank]
Company: [Blank]
Address: [Blank]
Phone #: [Blank]
Qualification: [Blank]
Date of Certification: [Blank]
Date of Renewal: [Blank]

LSSI | Section 2: SWPPP Overview Part I

69

SWPPP Documentation - *Static*

9. Duly Authorized Representative

Key inspection check: Who can sign reports or update the SWPPP for the Operator?

- LSSI: Again...could be MANY different people

Duly Authorized Representative

First Name: [Blank]
Last Name: [Blank]
Company: [Blank]
Address: [Blank]
Phone #: [Blank]
Qualification: [Blank]
Date of Certification: [Blank]
Date of Renewal: [Blank]

LSSI | Section 2: SWPPP Overview Part I

70

SWPPP Documentation - *Static*

10. SWPPP signature

Key inspection check: Is this the signed, official copy of the SWPPP?

- LSSI: Many SWPPP copies could be floating around

SWPPP signature

First Name: [Blank]
Last Name: [Blank]
Company: [Blank]
Address: [Blank]
Phone #: [Blank]
Qualification: [Blank]
Date of Certification: [Blank]
Date of Renewal: [Blank]

LSSI | Section 2: SWPPP Overview Part I

71

SWPPP Documentation - *Static*

1. General information

2. Approved ESC plan

3. Approved SWM plan

5. Impaired waters, or sediment/nutrient TMDL, + Exceptional

6. PCB impaired waters and TMDL requirements

8. Qualified personnel

9. Duly Authorized Representative

10. SWPPP signature

Questions???

LSSI | Section 2: SWPPP Overview Part I

72

ESC and SWM Plans


Section 3: What's the Plan??

Hands-on Activity –
Digging into an Erosion Control and Stormwater Management Plan

LSSI | Section 3: ESC and SWM Plans

73

Overview




LSI | Section 3: ESM Plan Reading



74

Plan Legend or Key

A small chart on the plan showing definitive line usage, specialized symbols, and scale.




LSI | Section 3: ESM Plan Reading



75

Existing, Proposed, Legend or Key




LSI | Section 3: ESM Plan Reading



76

Reading Contour Lines

- Existing contours are usually shown as lighter gray or dashed lines
- Proposed contours are usually shown as solid black lines



LSI | Section 3: ESM Plan Reading



77

Reading Contour Lines

- Contour lines indicate the steepness of the terrain
- The closer the lines are together = steeper terrain
- Further apart means less steep




LSI | Section 3: ESM Plan Reading




78

Slopes and Slope Calculations

Contour profiles



Concave vs. Convex



LSI | Section 3: ESM Plan Reading



79

Calculating Slope Steepness

- Choose two points of interest
- Find the elevation change (rise)
 - Subtract the two points of interest
- Measure the slope length (run)
- Divide rise/run
- Multiply by 100

$$\frac{(125 - 110)}{40} \times 100 = 37.5\% \text{ slope}$$

LSSI | Section 3: ESM Plan Reading




80

Slopes and Angles

- Slope percentage divides the vertical distance by the horizontal distance, then multiplies by 100.

$$-\frac{1}{3} \times 100 = 33.3\% \text{ slope}$$




LSSI | Section 3: ESM Plan Reading



81

Questions??



LSSI | Section 3: ESM Plan Reading



82

ESC Plan

Construction BMPs – VSMH Ch.7


- Structural practices
 - C-ECM** – Erosion Control Measures
 - C-ENV** – Environmentally Sensitive Area Protection
 - C-PCM** – Perimeter Control Measures
 - C-SCM** – Sediment Control Measures
 - For sediment control; *second* line of defense
- Vegetative practices
 - C-SSM** – Surface Stabilization Measures
 - For erosion control; *first* line of defense

LSSI | Section 3: ESM Plan Reading



83

Construction BMPs – VSMH Ch.7




LSSI | Section 3: ESM Plan Reading



84

ESC Plan



- What phase are they in?
 - Construction Sequence is critical!
- What measures are on the plan?
 - Proprietary Measures
- Where to start, and how to get where you need to go (*timing and route planning*)?
 - Entrances/roads, discharge points, sensitive areas
- Details, details, details


LSSI | Section 3: ESM Plan Reading




85

ESC Plan

Illustrative Construction Site Plan



ESC Notes and Details



LSSI | Section 3: ESM Plan Reading



86

Common ESC measures - LSSI



87

ESC Plan Symbology - C-ECMs

VSMH
Chapter 7:
Section 7.3

EROSION CONTROL MEASURES		
C-ECM-01 STRAW WATTLES	(SW)	← (SW) →
C-ECM-02 IMPERMEABLE DIVERSION FENCE	(IDF)	← (IDF) →
C-ECM-03 SLOPE INTERRUPTION DEVICE	(SID)	← (SID) →
C-ECM-04 TEMPORARY DIVERSION DIRT	(DD)	← (DD) →
C-ECM-05 DIVERSION	(D)	← (D) →
C-ECM-06 TEMPORARY FILL DIVERSION	(FD)	← (FD) →
C-ECM-01 STRAW WATTLES	(SW)	← (SW) →
C-ECM-09 STORMWATER CONVEYANCE CHANNEL	(SC)	← (SC) →
C-ECM-10 SUBSURFACE DRAIN	(SD)	← (SD) →
C-ECM-11 PAVED FLUME	(PF)	← (PF) →
C-ECM-12 TEMPORARY SLOPE DRAIN	(ML)	← (ML) →
C-ECM-13 SBRAP	(BR)	← (BR) →
C-ECM-14 TEMPORARY LEVEL SPREADER	(LS)	← (LS) →
C-ECM-15 OUTLET PROTECTION	(OP)	← (OP) →
C-ECM-16 FLEXIBLE TRANSITION MAT	(FM)	← (FM) →

LSSI | Section 3: ESM Plan Reading



88

ESC Plan Symbology - C-SCMs

VSMH
Chapter 7:
Section 7.3

SEDIMENT CONTROL MEASURES		
C-SCM-01 DUST CONTROL	(DC)	← (DC) →
C-SCM-02 CONSTRUCTION ROAD STABILIZATION	(CRS)	← (CRS) →
C-SCM-03 TEMP STONE CONSTRUCTION ENTRANCE	(CTSE)	← (CTSE) →
C-SCM-04 INLET PROTECTION	(IP)	← (IP) →
C-SCM-05 CULVERT INLET PROTECTION	(CIP)	← (CIP) →
C-SCM-06 WOOD CHIP FILTER BERM	(FCB)	← (FCB) →
C-SCM-07 ROCK CHECK DAMS	(CD)	← (CD) →
C-SCM-08 ROCK FILTER OUTLET	(RFO)	← (RFO) →
C-SCM-09 TURBIDITY CURTAIN	(TC)	← (TC) →
C-SCM-10 DEWATERING STRUCTURE	(DS)	← (DS) →
C-SCM-11 TEMPORARY SEDIMENT TRAP	(ST)	← (ST) →
C-SCM-12 TEMPORARY SEDIMENT BASIN	(SB)	← (SB) →
C-SCM-13 CONCRETE WASHOUT PIT	(CW)	← (CW) →

LSSI | Section 3: ESM Plan Reading



89

ESC Plan Symbology - C-SSMs

VSMH
Chapter 7:
Section 7.3

SURFACE STABILIZATION MEASURES		
C-SSM-01 TREE PRESERVATION AND PROTECTION	(TP)	← (TP) →
C-SSM-02 TOPSOILING	(TO)	← (TO) →
C-SSM-03 SURFACE ROUGHENING	(BR)	← (BR) →
C-SSM-04 COMPOST BLANKETS	(CB)	← (CB) →
C-SSM-05 SOIL STABILIZATION BLANKETS AND MATTING	(BMM)	← (BMM) →
C-SSM-06 SOODING	(SO)	← (SO) →
C-SSM-07 BERMUDAGRASS AND ZOYSAGRASS ESTABLISHMENT	(BEG)	← (BEG) →
C-SSM-08 TREES, SHRUBS, VINES, AND GROUND COVER	(VGC)	← (VGC) →
C-SSM-09 TEMPORARY SEEDING	(TS)	← (TS) →
C-SSM-10 PERMANENT SEEDING	(PS)	← (PS) →
C-SSM-11 MULCHING	(MU)	← (MU) →

LSSI | Section 3: ESM Plan Reading



90

ESC Plan Symbology - C-PCMs

VSMH
Chapter 7:
Section 7.3

PERIMETER CONTROL MEASURES		
C-PCM-01 SAFETY FENCE	(SAF)	← (SAF) →
C-PCM-02 STRAW BALE BARRIER	(SBB)	← (SBB) →
C-PCM-03 BRUSH BARRIER	(BB)	← (BB) →
C-PCM-04 SILT FENCE	(SF)	← (SF) →
C-PCM-05 COMPOST FILTER SOCK	(CFS)	← (CFS) →

LSSI | Section 3: ESM Plan Reading



91

ESC Plan Symbology - C-ENVs

VSMH
Chapter 7:
Section 7.3


ENVIRONMENTAL SENSITIVE AREA PROTECTION		
C-ENV-01 VEGETATIVE STREAMBANK STABILIZATION	(Symbol)	(Symbol)
C-ENV-02 STRUCTURAL STREAMBANK STABILIZATION	(Symbol)	(Symbol)
C-ENV-03 TEMPORARY VEHICULAR STREAM CROSSING	(Symbol)	(Symbol)
C-ENV-04 UTILITY STREAM CROSSING	(Symbol)	(Symbol)
C-ENV-05 CORRUGATED CROSSING	(Symbol)	(Symbol)
C-ENV-06 STABLE WETLAND CROSSING	(Symbol)	(Symbol)
C-ENV-07 GABION/LOGS DEFLECTORS	(Symbol)	(Symbol)
C-ENV-08 PUMP AROUND DIVERSION	(Symbol)	(Symbol)
C-ENV-09 OVERSIGHT CHANNEL PROTECTION	(Symbol)	(Symbol)
C-ENV-10 TRENCHLESS SILT FENCE	(Symbol)	(Symbol)
C-ENV-11 WETLAND BEAM	(Symbol)	(Symbol)
C-ENV-12 WETLAND WEIR OUTLET	(Symbol)	(Symbol)
C-ENV-13 WETLAND CELL SEDIMENT TRAP	(Symbol)	(Symbol)
C-ENV-14 MODIFIED TURBIDITY CURTAIN FOR STREAMS	(Symbol)	(Symbol)
C-ENV-15 SEDIMENT MUD CHAIN, AND SOIL STABILIZATION WETLANDS STREAMS	(Symbol)	(Symbol)

LSSI | Section 3: ESM Plan Reading



92

ESC Plan Considerations - Details




- Is there a detail for EVERY ESC measure?
- Is there sizing/dimensions, where required?
- Are there proprietary, or non-familiar practices?
- Does the field reflect the plan?

LSSI | Section 3: ESM Plan Reading



93

ESC Plan Considerations - Details



LSSI | Section 3: ESM Plan Reading



94

SWM Plan

Post Construction BMPs – VSMH Ch.8

- 17 Non-proprietary P-BMPs
 - P-BAS – Basins: Four (4) Measures
 - P-CNV – Conveyances: Four (4) Measures
 - P-FIL – Filtration/Infiltration: Nine (9) Measures
- Support Components
 - P-SUP: Six (6) Components
 - General information used across multiple P-BMPs

LSSI | Section 3: ESM Plan Reading



95

Post Construction BMPs – VSMH Ch.8



LSSI | Section 3: ESM Plan Reading



96

SWM Plan

- Locations of post-construction BMPs
 - Co-located BMPs
- Phased section and BMP installation timing?
 - What sections are older, newer, closed, etc.?
- How are the permanent measures labeled?
 - Are P-BMPs being protected during construction/installation?
- Are there critical areas/hotspots on site?
 - P-BMPs near fueling areas, soil stockpiles, heavy-traffic
- Plan details for materials, sequencing, storage capacity, final stabilization

LSSI | Section 3: ESM Plan Reading




97

SWM Plan

Post Construction Site Plan



SWM Notes and Details



LSI | Section 3: ESM Plan Reading



98


Common SWM P-BMPs - LSSI



99

Common SWM P-BMPs - LSSI

- Where are the P-BMPs that are getting converted?
 - What does conversion look like for EVERY P-BMP?
- Where are the sediment basins needing removal?



LSI | Section 3: ESM Plan Reading



100

Questions for Conversion


- Does conversion need to happen now?
- Does CONVERSION need to happen NOW?
- DOES CONVERSION NEED TO HAPPEN NOW?
- What does conversion look like?
 - Following sequence, final grading, outlet protection design, additional materials, As-builts, etc.
- Who is responsible for maintenance on installed SWM facilities during and after construction?

LSI | Section 3: ESM Plan Reading



101

Converting ESC to SWM




LSI | Section 3: ESM Plan Reading



102

Converting ESC to SWM



Outlet type changes?

LSI | Section 3: ESM Plan Reading



103

104

105

106

107

108

109

Site Plan Review Exercise




- Time to discuss what the group found!!




LSI | ESM Plan Reading

116




LSI | ESM Plan Reading

117




LSI | ESM Plan Reading

118




LSI | ESM Plan Reading

119



LSI | ESM Plan Reading

120




LSI | ESM Plan Reading

121


Important Info We Have Here?

- Adjacent Areas
- Offsite Areas – None
- Critical (sensitive) Areas
- ESC Maintenance Notes
- Construction Sequence!







122




123




124




125



126



127



128

Site Plan Review Exercise

Takeaways (LSSI):

- Know what you're getting into before you get there
- Plan a "best" route
- How many ESC measures? And Where...
- Discharge points!!!!
- What NEEDS to be removed?
- Permanent measure info is **critical** to check!
- O&M considerations for ongoing inspections?

LSSI | ESM Plan Reading

129

SWPPP Review Activity – Part II

Active SWPPP Sections

LSSI | Section 4: SWPPP Overview Part II

130

SWPPP Documentation - **Active**

1. General information	2. Approved ESC plan	3. Approved SWM plan
4. P2 plan	5. Impaired waters, or sediment/nutrient TMDL, + Exceptional	6. PCB impaired waters and TMDL requirements
7. Turbidity Monitoring Requirements	8. Qualified personnel	9. Duly Authorized Representative
10. SWPPP signature	11. SWPPP inspection records	12. Amendments, Modifications, & Updates

LSSI | Section 4: SWPPP Overview Part II

131

Quick Review: SWPPP *must* be updated

Question 1: How many days does the Qualified Personnel have to *include an inspection report* in the SWPPP once completed?

Question 2: How many days does the Operator (or Rep) have to *update* the SWPPP once a portion has changed or been modified?

Question 3: How many days does the Operator (or Rep) have to *complete* corrective actions or routine maintenance identified by a QP inspection?


Timeframe Requirement

- A1: 4 business days
- A2: 5 business days*
- A3: 5 business days*


****Longer period if approved by VESMP Authority**

LSSI | Section 4: SWPPP Overview Part II

132



133

SWPPP Documentation - *Active*
Pollution Prevention Plan (P2 Plan)[illegible]


Pollution Prevention (P2) Practices

- Must be *site specific* within a SWPPP
- Shall be followed to prevent pollutant releases
- Denotes all relevant, specific P2 practices
- P2 plans are not usually reviewed except by the *inspector on-site*
- Documentation updated as conditions change (P2 *measures added, moved, or removed from the site*)
- Inspection Point:
 - What and Where onsite?
 - Site and documentation match-up?



Concrete Washout Examples






Washout and cleanout of construction materials

Examples


- Area is **covered** (plastic sheeting or temporary roofs) to **prevent contact with stormwater**
- Adequate containment** is provided for the **amount** of wash water used
- Disposal** of waste solids and liquids is contract with a **hazardous waste disposal firm**

140

Paint and Other Construction Washout



LSSI | Section 4: SWPPP Overview Part II



141




Vehicle fueling and maintenance

Examples

- Secondary containment (spill berms, decks, spill containment pallets) is provided
- Cover is provided where appropriate
- Spill kits are readily available

142



Leak and spill prevention and response plan

- Procedures **must** be in place for quickly stopping, containing, and cleaning up spills, leaks, and other releases
- Procedures **must** be in place for documenting and/or reporting leaks, spills, and other releases

143

Spill Kit


- Verify Locations
 - Dedicated area?
 - Inside work truck?
 - Construction trailer?
- Check Contents
 - Adequate?
 - Restock needed?



LSSI | Section 4: SWPPP Overview Part II



144



Vehicle and equipment washing

Examples

- Washing activities located away from surface waters and stormwater inlets or conveyance and directing wash waters to sediment basins or traps
- Use of filtration devices such as filter bags or sand filters, or another similarly effective control

145

25

SWPPP Documentation - Active Turbidity Monitoring Requirements

Turbidity Benchmark Monitoring Data Table									
Project Name: No Commercial Development					Type/Event: See Notes				
Dewatering Activity (description and approximate location): Foundation dewatering - western part of project at building					Sample Location (description or wellhead number): See Note 1 - (west side of project)				
Turbidity Filter: None (none used/not used): None - Turbidity Filtered (none used/not used)					Turbidity Benchmark Option: DEQ P-1, 5, 10, 15				
Sample Collection		Turbidity Results		Turbidity Benchmark		Notes (including weather conditions)			
Name of Individual Conducting Monitoring - (last, first)	Date	Time	Turbidity (NTU)	Sample Location (Wellhead #)	Sample Date/Time	Notes	Weather	Time	Time
MMO/MSD	10/10/24	10:00AM	3.0	NTU	Yes	No	Clear, no wind	10:00AM	10:00AM
MMO/MSD	10/10/24	10:00AM	4.5	NTU	Yes	No	Fog, light, mostly clear	10:00AM	10:00AM
MMO/MSD	10/10/24	10:00AM	4.2	NTU	Yes	No	Fog, light, mostly clear	10:00AM	10:00AM

Three Benchmark Options:

1. ≤ 50 NTU/FTUs of upstream grab sample
2. ≤ 150 NTU/FTUs
3. ≤ 50 NTU/FTUs of a weekly turbidity average
4. Alternative, DEQ-approved method

LSSI | Section 4: SWPPP Overview Part II



152

Turbidity Benchmark Monitoring Data Table									
Project Name: No Commercial Development					Type/Event: See Notes				
Dewatering Activity (description and approximate location): Foundation dewatering - western part of project at building					Sample Location (description or wellhead number): See Note 1 - (west side of project)				
Turbidity Filter: None (none used/not used): None - Turbidity Filtered (none used/not used)					Turbidity Benchmark Option: DEQ P-1, 5, 10, 15				
Sample Collection		Turbidity Results		Turbidity Benchmark		Notes (including weather conditions)			
Name of Individual Conducting Monitoring - (last, first)	Date	Time	Turbidity (NTU)	Sample Location (Wellhead #)	Sample Date/Time	Notes	Weather	Time	Time
MMO/MSD	10/10/24	10:00AM	3.0	NTU	Yes	No	Clear, no wind	10:00AM	10:00AM
MMO/MSD	10/10/24	10:00AM	4.5	NTU	Yes	No	Fog, light, mostly clear	10:00AM	10:00AM
MMO/MSD	10/10/24	10:00AM	4.2	NTU	Yes	No	Fog, light, mostly clear	10:00AM	10:00AM

Turbidity - Questions

- Activity locations; dewatering, discharge, and sampling?
- Proper methods, timing, and equipment?
- Issues or exceedances, and Corrective Actions needed?
- Adequate monitoring documentation

153


- Dewatering Operations Discharges
→ REQUIRE turbidity monitoring

Turbidity Monitoring - LSSI

- Multiple dewatering operations at different times
- Different waterways
- Documentation/Corrective Actions?

154

SWPPP Documentation - Active Turbidity Monitoring Requirements



- EPA Guide for Construction Dewatering
 - <https://www.epa.gov/system/files/documents/2022-01/cgp-inspection-and-monitoring-guide-for-dewatering.pdf>
- EPA Turbidity Monitoring under the Federal Construction General Permit:
 - <https://www.epa.gov/npdes/turbidity-benchmark-monitoring-dewatering-under-construction-general-permit>

LSSI | Section 4: SWPPP Overview Part II



155

SWPPP Documentation - Active Inspection Reports; Inspection/CA Log

DEQ Design & Associates

Qualified Personnel Inspection Report

Project: **SWPPP Overview Part II**

Date: **10/10/24**

Inspection Schedule: **10/10/24**

Inspection Results: **Pass**

Notes: **Substation is the northeast section of the site. All dewatering operations are contained within the site. No dewatering operations are visible outside the site. No dewatering operations are visible outside the site.**

Inspection/Corrective Action Log

Inspection Date	Corrective Action Item	Completed Date
10/10/24	Substation is the northeast section of the site. All dewatering operations are contained within the site. No dewatering operations are visible outside the site. No dewatering operations are visible outside the site.	10/10/24
10/10/24	Substation is the northeast section of the site. All dewatering operations are contained within the site. No dewatering operations are visible outside the site. No dewatering operations are visible outside the site.	10/10/24
10/10/24	Substation is the northeast section of the site. All dewatering operations are contained within the site. No dewatering operations are visible outside the site. No dewatering operations are visible outside the site.	10/10/24
10/10/24	Substation is the northeast section of the site. All dewatering operations are contained within the site. No dewatering operations are visible outside the site. No dewatering operations are visible outside the site.	10/10/24

LSSI | Section 4: SWPPP Overview Part II



156

DEQ Design & Associates

Qualified Personnel Inspection Report

Project: **SWPPP Overview Part II**

Date: **10/10/24**

Inspection Schedule: **10/10/24**

Inspection Results: **Pass**

Notes: **Substation is the northeast section of the site. All dewatering operations are contained within the site. No dewatering operations are visible outside the site. No dewatering operations are visible outside the site.**

Inspection/Corrective Action Log

Inspection Date	Corrective Action Item	Completed Date
10/10/24	Substation is the northeast section of the site. All dewatering operations are contained within the site. No dewatering operations are visible outside the site. No dewatering operations are visible outside the site.	10/10/24
10/10/24	Substation is the northeast section of the site. All dewatering operations are contained within the site. No dewatering operations are visible outside the site. No dewatering operations are visible outside the site.	10/10/24
10/10/24	Substation is the northeast section of the site. All dewatering operations are contained within the site. No dewatering operations are visible outside the site. No dewatering operations are visible outside the site.	10/10/24
10/10/24	Substation is the northeast section of the site. All dewatering operations are contained within the site. No dewatering operations are visible outside the site. No dewatering operations are visible outside the site.	10/10/24

SWPPP Inspections - Q1

Is the required inspection frequency being followed?

157

DEQ Design & Associates

Qualified Personnel Inspection Report

Project: **10/15/24** Time of Inspection: **10/15/24**

Inspection Schedule

Inspection Date	Inspector	Time of Inspection	Inspection Results
10/15/24	Phonetic	10:00 AM	Prohibited discharge of sediment or other pollutants into the water body. <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
10/15/24	Phonetic	10:00 AM	Prohibited discharge of sediment or other pollutants into the water body. <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
10/15/24	Phonetic	10:00 AM	Prohibited discharge of sediment or other pollutants into the water body. <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
10/15/24	Phonetic	10:00 AM	Prohibited discharge of sediment or other pollutants into the water body. <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No

SWPPP Inspection Schedule
(SWPPP-5.000-10 Part (B.2) and Part (C.2))

Discharges to Impaired waters, surface waters with an applicable IMDI or exceptional waters

Inspections must be conducted either:

- At least once every **5 business days**; or
- At least once every **5 business days** and no later than **24 hours** following a measurable storm event.

Standard Inspections

Inspections must be conducted either:

- At least once every **5 business days**; or
- At least once every **5 business days** and no later than **24 hours** following a measurable storm event.

SWPPP Inspections – Answer
Second inspection done at a 5 day interval (should be 4 day).

158

DEQ Design & Associates

Inspection/Corrective Action Log

Inspection Date	Inspector	Time of Inspection	Inspection Results
10/15/24	Phonetic	10:00 AM	Prohibited discharge of sediment or other pollutants into the water body. <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
10/15/24	Phonetic	10:00 AM	Prohibited discharge of sediment or other pollutants into the water body. <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
10/15/24	Phonetic	10:00 AM	Prohibited discharge of sediment or other pollutants into the water body. <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
10/15/24	Phonetic	10:00 AM	Prohibited discharge of sediment or other pollutants into the water body. <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No

SWPPP Inspections – Q2
Are the inspection reports in the copy of the SWPPP signed by the correct site personnel?

159

DEQ Design & Associates

Inspection/Corrective Action Log

Inspection Date	Inspector	Time of Inspection	Inspection Results
10/15/24	Phonetic	10:00 AM	Prohibited discharge of sediment or other pollutants into the water body. <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
10/15/24	Phonetic	10:00 AM	Prohibited discharge of sediment or other pollutants into the water body. <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
10/15/24	Phonetic	10:00 AM	Prohibited discharge of sediment or other pollutants into the water body. <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
10/15/24	Phonetic	10:00 AM	Prohibited discharge of sediment or other pollutants into the water body. <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No

SWPPP Inspections – Q2
Answer
Inspection on 11/7/24 not signed by the DAR. Signed only by QP.

160

DEQ Design & Associates

Inspection/Corrective Action Log

Inspection Date	Inspector	Time of Inspection	Inspection Results
10/15/24	Phonetic	10:00 AM	Prohibited discharge of sediment or other pollutants into the water body. <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
10/15/24	Phonetic	10:00 AM	Prohibited discharge of sediment or other pollutants into the water body. <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
10/15/24	Phonetic	10:00 AM	Prohibited discharge of sediment or other pollutants into the water body. <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
10/15/24	Phonetic	10:00 AM	Prohibited discharge of sediment or other pollutants into the water body. <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No

SWPPP Inspections – Q3
Are Corrective Actions being identified, and addressed from one inspection to the next within the required timeframe?

161

DEQ Design & Associates

Inspection/Corrective Action Log

Inspection Date	Inspector	Time of Inspection	Inspection Results
10/15/24	Phonetic	10:00 AM	Prohibited discharge of sediment or other pollutants into the water body. <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
10/15/24	Phonetic	10:00 AM	Prohibited discharge of sediment or other pollutants into the water body. <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
10/15/24	Phonetic	10:00 AM	Prohibited discharge of sediment or other pollutants into the water body. <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
10/15/24	Phonetic	10:00 AM	Prohibited discharge of sediment or other pollutants into the water body. <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No

SWPPP Inspections – Q3
Discharge on 10/31 not addressed until 11/9 (nine calendar days)

162

What's Going On?

Inspection Report – Corrective Actions

- Reviewing CA Log or individual Inspection Reports?
- What's been done within the 5 bus-day timeframe, and what HASN'T?
- Items passed 5 bus-day;
 - Been addressed?
 - Yes, but not signed off on
 - Or, NOT been addressed (VESMP approval?)

SWPPP Overlap (IR +):

- Prohibited Discharges
 - AMUS
- Additional P2/ESC Controls
 - P2 plan and/or AMUS
- Turbidity Exceedances
 - Turbidity Monitoring Section, AMUS
- Required stabilization of denuded areas
 - AMUS

LESSI | Section 4: SWPPP Overview Part II



163

What's Going On?

Every site

- Who has been inspecting for the Operator (QPs)?
- Reports signed appropriately?
- What/Where were the issues?
- Following inspection frequency?
- Are there previous issues addressed within timeframe?
- Reports reflect site conditions?
 - Additional/modified controls?

LSI Considerations

- How have QPs been inspecting?
 - One full day or multi-day (more, separate reports)
- Multiple inspectors
- Cumbersome IR review

SWPPP Inspection Schedule (VAC 22-800-70 Part 1 B.6.6 and Part 1 B.6.7)

Discharges to impaired waters, surface waters with an applicable TMDL, or exceptional waters	Standard Inspections
Inspections must be conducted either: 1. At least once every 5 business days or 2. At least once every 3 business days and no later than 24 hours following a measurable storm event	Inspections must be conducted either: 1. At least once every 5 business days or 2. At least once every 10 business days and no later than 24 hours following a measurable storm event

LSI | Section 4: SWPPP Overview Part II

164

What's Going On?

QP Inspection Report Review – Inspection **4/15**

QP report observation/ Date observed	Corrective Action/Due Date	Date Completed/Operator Signature
SF down in SW corner, behind SB-1	4/7	Repair/replace SF as needed, per approved ESC plan 4/14
Erosion on east slope of ST-3	4/11	Repair/regrade erosion area, apply stabilization 4/18
		Item to check on next inspection

LSI | Section 4: SWPPP Overview Part II

165

What's Going On?

QP Inspection Report Review – Inspection **6/10**

QP report observation/ Date observed	Corrective Action/Due Date	Date Completed/Operator Signature
SF down in SW corner, behind SB-1	4/7	Repair/replace SF as needed, per approved ESC plan 4/14
Erosion on east slope of ST-3	4/11	Repair/regrade erosion area, apply stabilization 4/18
OP for SB-3 not installed per ESC plan	5/13	5/13
SF undermined behind ST-1, SE corner	5/15	Repair and backfill undermined SF sections 5/22

Check CA Log, and/or previous reports back to 5/5

LSI | Section 4: SWPPP Overview Part II

166

What's Going On? → LSSI Example

QP Inspection Report Review – Inspection **4/15**

QP report observation/ Date observed	Corrective Action/Due Date	Date Completed/Operator Signature
SF down in SW corner, behind SB-1	4/7	Repair/replace SF as needed, per approved ESC plan 4/14
Erosion on east slope of ST-3	4/11	Repair/regrade erosion area, apply stabilization 4/18
		Item to check on next inspection

How are Large Sites any different?

LSI | Section 4: SWPPP Overview Part II

167

What's Going On? → LSSI Example

QP Inspection Report Review – Inspection **6/10**

QP report observation/ Date observed	QP report observation/ Date observed	QP report observation/ Date observed	QP report observation/ Date observed
SF down in SW corner of section G, behind SB-13	ST-6 not stabilized immediately once installed	SF torn/down along SE perimeter of	Section C; RCDs in swales near ST-8 full
Erosion on east slope of SB-6	En slope of SB-6	En slope of SB-6	En slope of SB-6
OP for SB-3 not installed per ESC plan	Culvert IP not installed at crossing of sections B and C	Fabric liner not installed in outfalls: ST-4, 6, 7, and 11	Upslope grading prior to ESC controls in Section H
SF undermined behind ST-1, SE corner	SB-14 riser does not have dewatering device	CWO washwater outside of container, SE area of section B	Hydraulic fuel uncontained on ground near CE-3

!!! Issues can pile up over time with SO MUCH activity !!!

LSI | Section 4: SWPPP Overview Part II

168

What's Going On? → LSSI Example

QP Inspection Report Review – Inspection **4/15-6/10**

Observations	Corrective Actions	Date Completed/Op. Sign
Issue 1 4/17	CA-1 4/24	1 4/24 Operator
Issue 2 4/17	CA-2 4/24	2 4/22 Operator
Issue 3 4/23	CA-3 4/30	3 4/25 Operator
Issue 4 4/29	CA-4 5/6	4 4/30 Operator
Issue 5 4/29		5 5/5 Operator
Issue 6 5/5		6
Issue 7 5/9		7 5/13 Operator
Issue 8 5/9		8 5/13 Operator
Issue 9 5/15	CA-9 5/22	9 5/22 Operator
Issue 10 5/15	CA-10 5/22	10 5/19 Operator
Issue 11 5/21	CA-11 5/28	11 5/27 Operator
Issue 12 5/27	CA-12 6/3	12 6/1 Operator
Issue 13 5/27	CA-13 6/3	13 6/1 Operator
Issue 14 6/2	CA-14 6/9	14


What could be happening....

LSI | Section 4: SWPPP Overview Part II

169

What's Going On? → *LSSI Example*


QP Inspection Report Review – Inspection 4/15-6/10



Best Practices????

- Note dates of missing info and CA date → Cross-reference CA log and/or individual reports
- Take pictures of SWPPP pages for later reference

LSSI | Section 4: SWPPP Overview Part II




170

What's Going On? → *LSSI Example*


QP Inspection Report Review – Inspection 4/15-6/10

Next Steps?

- Check old IRs for repeat CAs (>5 days)
- Inquire with Operator, Reps, and/or QPs
- Ground Truth!
- ALWAYS, ALWAYS... **WALK THE SITE!!**




LSSI | Section 4: SWPPP Overview Part II




171

SWPPP Documentation - Active Amendments, Modifications, & Updates




- SWPPP change potentially effecting pollutant discharge
- Additional/modified P2/ESC measures to address ineffective controls
- Identify Responsible Contractors
- SWPPP Updates:
 - Major grading
 - LDA ceases on a portion of the site
 - Stabilization measures applied
 - Final stabilized areas (no inspections required)
 - Areas no longer under Operator control
 - Prohibited discharge information

LSSI | Section 4: SWPPP Overview Part II



172


SWPPP Documentation - Active Amendments, Modifications, & Updates



Alternative Recordkeeping:

- AMUs (and other SWPPP sections) may come in different varieties depending on what template being used:
 - Grading Log
 - Land Disturbance Log
 - Porta-John Tracking
 - Prohibited Discharge Log
 - Cutsheet Updates
 - Other Examples?

LSSI | Section 4: SWPPP Overview Part II




173


SWPPP Documentation - Active Amendments, Modifications, & Updates

LSSI Key Points:

- What ESC measures have(not) been installed?
- Co-located/ Conversion to SWM facilities
- Hotspots – added controls
- ESC no longer needed (removed)
- DENUDED AREAS**
 - Grading
 - Stabilization



LSSI | Section 4: SWPPP Overview Part II




174

What's Going On?

Every site	LSSI Considerations
SWPPP Overlap (IR +): <ul style="list-style-type: none"> Prohibited Discharges <ul style="list-style-type: none"> AMUs Additional P2/ESC Controls <ul style="list-style-type: none"> P2 plan and/or AMUs Turbidity Exceedances <ul style="list-style-type: none"> Turbidity Monitoring Section, AMUs Required stabilization of denuded areas <ul style="list-style-type: none"> AMUs 	<ul style="list-style-type: none"> Cumbersome document review Even MORE documentation overlap New sections opened? <ul style="list-style-type: none"> Increases inspection area(time) Stabilized sections closed? <ul style="list-style-type: none"> Older sections may not need inspecting once fully stabilized ESC→SWM considerations

LSSI | Section 4: SWPPP Overview Part II



175

SWPPP Overview: Key Points and Considerations

- Is Everything There? (*take your time*)
- Who's WHO?? (QP, Duly Authorized Rep, Operator, subcontractors, 3rd party, localities)
- Corrective Actions? ...Perfect Inspections?!
- Alternative Recordkeeping: *Grading Log, Cutsheet updates, Multiple SWPPP binders, etc.*
- Documentation: More is Better...Sort of



LSSI | Section 4: SWPPP Overview Part II



182

SWPPP Overview: Key Points and Considerations

- Summary of best management practices
 - Take enough time to understand documentation
 - Take notes and pictures of documents, especially missing info
 - Organize notes and pictures to easily reference later without confusion
 - Cross-reference missing information with other sections of the SWPPP (Ex: IRs and AMUs)
 - Talk with interested parties (QPs, Operator, etc.) to ensure a compliance strategy can be accomplished

LSSI | Section 4: SWPPP Overview Part II



183


Large Scale Site Inspection – Section 5

Boots on the Ground



184

Document




Application



185

Document



SEDIMENT TRAP TO PERMANENT DETENTION BASIN SEQUENCE

1. DRAINAGE BASINS AND MUCK OUT BUILT. DRAINAGE OF THE A NON-ROBBLE MANNER WITH THE USE OF A DIRT BAG OR BRING BOTTOM OF BASIN TO PERMANENT GRADE. IF NECESSARY
2. REMOVE TEMPORARY PLATE ON PIPE AND INSTALL PERMANENT
3. REMOVE STONE OUTLET AND INSTALL PERMANENT EMBANKMENT
4. APPLY PERMANENT SEEDING TO ALL DISTURBED AND/OR PIPE BASIN CONVERSIONS SHALL BE CERTIFIED BY A PROFESSIONAL GENERAL CONSTRUCTION PERMIT IS TERMINATED



Application



186

Prohibition of Non-stormwater Discharges

- Look out for the following prohibited discharges!
- If you see any, take pictures and note them on your inspection report
- Larger sites have **more** potential pollution issues


LSSI | Section 5: Boots on the Ground



187



188



189



190



191



192

Construction BMPs – VSWHB Ch.7

- Structural practices
 - C-ECM – Erosion Control Measures
 - C-ENV – Environmentally Sensitive Area Protection
 - C-PCM – Perimeter Control Measures
 - C-SCM – Sediment Control Measures
 - For sediment control; *second* line of defense
- Vegetative practices
 - C-SSM – Surface Stabilization Measures
 - For erosion control, *first* line of defense

LSSI | Section 5: Boots on the Ground



193

Erosion Control Measures (ECM)

- Prevent sheet, rill and gully erosion
- Reduce the overland flow velocities
- Shorten the length of flow
- Divert and convey runoff safely through a site

LSSI | Section 5: Boots on the Ground



194

Erosion Control Measures (ECM)

Diversions/Diversion Dikes



Slope Interruption Devices



LSSI | Section 5: Boots on the Ground



195

Erosion Control Measures (ECM)

Outlet Protection



Slope Drains



LSSI | Section 5: Boots on the Ground



196

Environmentally Sensitive Area Protection (ENV)

- Used in environmentally sensitive areas (stream corridors, wetlands, floodplains)
- Applied where disturbance in an environmentally sensitive area is necessary

LSSI | Section 5: Boots on the Ground



197

Environmentally Sensitive Area Protection (ENV)

Stream Crossings



Pump Around Diversions



LSSI | Section 5: Boots on the Ground



198

Perimeter Control Measures (PCM)

- Intercept sheet flow from slopes
- Remove sediment and other contaminants through:
 - Ponding
 - Settling
 - Physical filtration
- Prevent contaminants from leaving the site

LSSI | Section 5: Boots on the Ground



199

Perimeter Control Measures (PCM)

Silt Fence/Super Silt Fence



Filter Socks/Logs



LSSI | Section 5: Boots on the Ground



200

Sediment Control Measures (SCM)

- Prevent sediment from leaving the site
- Capture or filter sediment particles

LSSI | Section 5: Boots on the Ground



201

Sediment Control Measures (SCM)

Rock Check Dams



Dust Control



LSSI | Section 5: Boots on the Ground



202

Sediment Control Measures (SCM)

Rock Filter Outlet



Dewatering/Filtering Operations



LSSI | Section 5: Boots on the Ground



203

Sediment Control Measures (SCM)

Sediment Traps



Sediment Basins



LSSI | Section 5: Boots on the Ground



204

Sediment Control Measures (SCM)

Sediment Basin - Alternative



Concrete Washout



http://stormwater.pca.state.mn.us/index.php?title=Construction_storage_water_treatment_-_dewatering_including_chemical_treatment_and_sediment_filtration

LSSI | Section 5: Boots on the Ground



205

Surface Stabilization Measures (SSM)

- Protect disturbed soil from surface runoff
- Both temporary covering and permanent vegetative cover
- Often part of the final landscape

LSSI | Section 5: Boots on the Ground




206

Surface Stabilization Measures (SSM)

Erosion Matting



Surface Roughening




LSSI | Section 5: Boots on the Ground



207

Surface Stabilization Measures (SSM)

Temporary Stabilization



Permanent Stabilization




LSSI | Section 5: Boots on the Ground



208

Construction BMPs – ESC Issues

- Document Observations:
 - Which measure?
 - Detail issues; knocked down/damaged/doesn't work
 - Following plan?
 - WHERE IS IT?!



209

Questions?

210

Post-Construction BMP Overview

Basins – P-BAS

Constructed Wetlands
Wet Pond
Extended Detention Pond
Rainwater Harvesting

Conveyance – P-CNV

Grass Channels
Dry Swales
Wet Swales
Regenerative Stormwater Conveyance

LSSI | Section 5: Boots on the Ground




211

Post-Construction BMPs Categories

Filtration and Infiltration – P-FIL	Support Components – P-SUP
<ul style="list-style-type: none"> Rooftop/Impervious Surface Disconnection Vegetated Roof Permeable Pavement Infiltration Practice Bioretention Filtering Practices Sheet Flow to Vegetated Filter Strip/Conserved Open Space Soil Compost Amendment Tree Planting 	<ul style="list-style-type: none"> Earthen Embankment Principal Spillway Vegetated Emergency Spillway Pretreatment Quantity-Only Approach to BMPs

LSSI | Section 5: Boots on the Ground




212

Post-Construction MTD Categories

Hydrodynamic Devices – MTD-H	Filtering Devices – MTD-F	Biofilter Devices – MTD-B
<p>15 devices currently approved</p>	<p>13 devices currently approved</p>	<p>11 devices currently approved</p>

LSSI | Section 5: Boots on the Ground




213

Basins (P-BAS)

- Designed to detain or impound runoff
- Typically provide little to no infiltration
- Provide treatment through settling, runoff reduction and biologic uptake


LSSI | Section 5: Boots on the Ground




214

Basins (P-BAS) – LSSI common


Wet Pond



ED Pond



LSSI | Section 5: Boots on the Ground




215

Conveyance (P-CNV) 8.3.2

- Designed to receive a sustained concentrated flow of runoff or cross significant changes in grade
- Typically provide filtration, infiltration and settling within the conveyance system.


LSSI | Section 5: Boots on the Ground




216

Conveyance (P-CNV) – LSSI common


Grass Channels/Dry Swales



Wet Swales



LSSI | Section 5: Boots on the Ground



217

Filtration and Infiltration (P-FIL) 8.3.3

- P-FIL practices are designed to filter runoff through a natural or engineered media, returning any remaining runoff to a drainage system or infiltrating into native soils

LSSI | Section 5: Boots on the Ground



218

Filtration and Infiltration (P-FIL) – LSSI common

Bioretention



Sheet Flow to COS



LSSI | Section 5: Boots on the Ground



219

Support Components (P-SUP)

- Provide more generalized information that can be used across multiple different P-BMPs
- To be used in combination with other P-BMPs described in this Handbook

LSSI | Section 5: Boots on the Ground



220

Support Components (P-SUP)



LSSI | Section 5: Boots on the Ground



221

P-SUP-06 Pre-Treatment

1.0 Definition

- Practices that support the operation and maintenance of stormwater assets
 - Prolong the lifespan
 - Slow the velocity of flow

LSSI | Section 5: Boots on the Ground



222

P-SUP-06 - 3.0 Planning and Considerations

- Site conditions determine which pre-treatment practices are best-suited to different situations:

Table P-SUP-06-1 Pretreatment Selection Matrix

BMP	Roof Stormwater Isolation	Limit Hydraulic Loading	Treatment Train	Sediment Forebays	Grass Channels & Filter Strips	Reverse Slope Bench	Inlet Sump	Manufactured Devices	Sumped Inlet with Traps or Filters
Grass Channel	+								
Filtration Practices	+	+	+	+	+	+	+	+	+
Bioretention	+	+	+	+	+	+	+	+	+
Dry Swales	+	+	+	+	+	+	+	+	+
Wet Swales	+	+	+	+	+	+	+	+	+
Filtering Practices		+	+	+	+	+	+	+	+
Wet Ponds			+	+	+	+	+	+	+
Extended Detention Ponds			+	+	+	+	+	+	+
Regenerative Swale			+	+	+	+	+	+	+
Conveyance			+	+	+	+	+	+	+
Constructed Wetlands		+	+	+	+	+	+	+	+
Rainwater Harvesting	+	+						+	+

- Construction and maintenance information is based on selected measure

LSSI | Section 5: Boots on the Ground



223

P-SUP-08 Permanent Level Spreader





- Flow control measure that receives concentrated flow and converts to sheet flow condition
- Common measure for large sites
- Construction/maintenance is critical
- Typically FINAL measure before stormwater discharges site

LSSI | Section 5: Boots on the Ground



224

Section 7.0 Operations and Maintenance Considerations



- Maintain the level spreader lip at zero grade
- Inspect for low points, sags, cracks, breaks, etc. that would result in concentrated flow
- Remove debris accumulation when it reaches 20%

LSSI | Section 5: Boots on the Ground



225

Planting Guidance – Appendix G

Plant Type – Divided into the following categories:

- Canopy Trees
- Understory Trees
- Shrubs
- Flowering Perennials
- Grasses and Groundcovers
- Green Roof Plants

Canopy Trees

					Shallow roots can inhibit other plant growth. Prioritize culture.	
Acer rubrum					Early Winter	
Red Maple					March-April	
3 to 9'	60' x 40'	1 to 5			April-July	

LSSI | Section 5: Boots on the Ground



226

Questions?

227

Group Activity

Site walk:

Documenting observations at inspection stations



228


Site Walk Exercise

- Let's INSPECT!!
- **8 Stations** across the "site"
- Each group has **5 minutes** per station to document observations (40 min. tot.)


Station 1	
Picture 1	Observations, etc...
Picture 2	Observations, etc...
Picture 3	Observations, etc...




229




230




231




232



233



234



235

Station 5: Summary


1. P2 concerns
2. No inlet protection
3. Potential pollutant release
4. Erosion/IP issues
5. SF installation problem
6. Sediment deposition in channel
7. Decent stabilization
8. SB failure
9. SB failure cont...thoughts??



236

Station 6: Summary


1. CWO...bad
2. Silt fence down – repair
3. Good P2 implementation
4. Decent TS around stockpile
5. Mix of good and bad
6. OP needed
7. Erosion....
8. Also erosion – concentrated in channels, off-site or on-site
9. SB; wet storage? Other issues??



237

Station 7: Summary

1. Mud-tracking out of CE
2. Stabilization issues on ST
3. What could be wrong here????
4. IP is not adequate
5. Possible stabilization issues?
6. Is this an ESC measure...or a hole?
7. P2 measures look pretty solid
8. Inlet protection pretty decent



238

Station 8: Summary

1. SB needs stabilization
2. Rock filter outlet looks decent
3. Perimeter control installation
4. SB installation ongoing – OK?
5. P2 containment successful
6. IP; weird design – check plan
7. Perimeter access ongoing – thoughts??
8. Stabilization above pipe



239

Site Walk Review

- LSSI Takeaways:
 - So many issues to find
 - How many??
 - A LOT to “ground truth” from SWPPP
 - Route/site walk planning and timing critical
 - Typically, a lot to follow-up with on subsequent inspections




240

THANK YOU ALL!

Nick Shrewsbury, DEQ OTS
 Nicholaus.shrewsbury@
 deq.virginia.gov

CATS/ELMS Questions:
 certification@
 deq.virginia.gov



241